OAK RIDGE SUBDIVISION HOME BUILDING PLANS

LIME

BEDROOMS 3 BATHROOMS 2.5



DWELLING	SQ FT.	DWELLING	SQ. FT.
Ground Storage	N/A	Porches	217
1st Living	1,525	Parking / Open Storage	1,742
Enclosed Subtotal	1,525	Total Under Beam	3,484

PEBBLE LLC

OAK RIDGE SUBDIVISION HOME BUILDING PLANS

LIME

BEDROOMS BATHROOMS



FLOOR PLAN



OAK RIDGE SUBDIVISION HOME BUILDING PLANS

TYPICAL FINISH SCHEDULE - may vary from plan to plan -

ROOM FLOORS ALLOWANCE
Kitchen, Family/Living, Dining Vinyl Plank \$3.50/SF

All Baths & Utility

Ceramic tile

\$6.50/SF, Labor and Material

All Bedrooms & Closets

Carpet

\$23.00/SY, Labor and Material

Parking Area Concrete
Porches Treated wood

COUNTERTOPS: All countertops are made of 2cm granite

CABINETS: Custom, all wood, recessed maple painted Shaker cabinets

MASTER TUB: 6-foot soaking tub

MASTER SHOWER: Man-made marble shower floor & walls with tempered glass door

GUEST BATH: 5-foot cast iron tub with a man-made marble alcove finisehd to 7 feet

APPLIANCE ITEMS:

30" Self Cleaning range, stainless finish Vented hood, stainless finish Dishwasher, stainless finish

Disposal, 1/2 hp Microwave Drawer

MODEL#:

GE JV348 GE GSD 4060 GE GFC 525

MILLWORK:

INTERIOR DOORS:

Solid core masonite w/ 3 1/4 finger jointed casing

WINDOW TRIM:

Stool - apron - casing. All windows trimmed out

BASE: 7 1/4" Colonial MDF material
SHOE: 3/4" quarter round wood
CROWN: 4 5/8" Colonial MDF material

CASING: 3 ¼" Colonial wood HARDWARE: Sea Cliff - bronze WIRE SHELVING: \$500 Allowance

SHUTTERS:

All shall be fixed, aluminum, pre-finish units

SHELVING:

All closets w/ coated-wire shelving material.

PAINTING:

The exterior Hardi material shall receive one primer coat placed over the factory primed board and one finish coat of paint. The interior ceilings shall receive one coat of flat latex. The walls shall receive a prime coat then a rolled-on finish coat of latex paint. All case work shall receive two coats of an oil-base material.

